

4-071083

2-3

01  
①

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-01,028

NW NE SW /4 SEC. 21 , 09 S, 21 W  
2310 feet from S section line  
1650 feet from W section line

Operator license# 3631

Lease Darnell well #2 OWWO

Operator: Arrowstar Production Company

County Graham

Address: P.O. Box 458  
Ness City, Kansas 67560  
Fred J. Hembree

Well total depth 850 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 260 feet

35.00

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cementing - Hembree Well Serv. License#     

Address: Hays, Kansas 67601 - Ness City, Kansas 67560

Company to plug at: Hour: P.M. Day: 3 Month: February Year: 94

Plugging proposal received from: Fred Hembree - Herb Deines

Company: Arrowstar Prod. Co. - KCC Dist.#4 Phone: 913-798-3408

Were: 9 5/8" - 260' S.P. cwc. w/NA. 5 1/2" casing set @ 3780' w/NA.  
Original T.D. - 3786' open hole 6' (operator only got to 860'). Couldn't  
get down and decided to plug out well. Proposal 125 sxs. 60/40 pozmix -  
8% gel and 2 sxs. hulls. Spot and displace all cement through tubing.  
Load both 5 1/2" casing and 5 1/2" x 8 5/8" annulus with cement.

2-21-94

Plugging Proposal Received by: Marion J. Schmidt - Herb Deines  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 21 1994  
CONSERVATION DIVISION  
Wichita, Kansas

Completed: Hour: 3:45 P.M., Day: 3, Month: February, Year: 94

Actual plugging report: Arrowstar Production Company ordered 125 sxs.  
60/40 pozmix - 8% gel and 2 sxs. hulls. Pumped in with pump truck,  
spotted and displaced all cement through tubing.

- 1) 2 3/8" tubing at 820' w/70 sxs. cement with 1 sx. hulls added. Cement  
circulated out of 5 1/2" casing. Squeezed 5 1/2" casing with 5 sxs.  
cement. Max. pressure 300 P.S.I. Shut in at 150 P.S.I.
- 2) Squeezed 5 1/2" x 8 5/8" annulus with 50 sxs. cement with 1 sx. hulls.  
Max. pressure 300 P.S.I. Shut in at 200 P.S.I. By: Allied Cementing.

Remarks: (OWWO) During re-entry Arrowstar hit a bad spot at 850'.  
Condition of casing(in hole): GOOD      BAD X Anhy. plug: YES NR NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES NR, NO       
Plugged through TUBING X, CASING     . Elevation:      GL     

I did not observe the plugging.

*Marion J. Schmidt*  
(agent)

INVOICED  
DATE FEB 22 1994  
INV. NO. 39984  
2-3