

10-14

4-070070

15-065-01455-00-00

API Number: 15- -

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE SW NW /4 SEC. 21 09 S, 21 W
4290 feet from E section line
3630 feet from S section line

Operator license# 7076

Lease: Andreson B Well # ~~B-4~~

Operator: Black Diamond Oil, Inc.

County: Graham 123.92

Address: P.O. Box 641
Hays, Kansas 67601

Well total depth 3813 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 Inch @ 123 feet
W/125 sxs.

ABAND. oil well X, Gas well, Input well, SWD, D&A

Plugging contractor: Black Diamond Oil, Inc. License# 7076

Address: P.O. Box 641 - Hays, Kansas 67601

Company to plug at: Hour: 10:00 A.M. Day: 14 Month: October Year: 1997

Plugging proposal received from: Ken Vehgie

Company: Black Diamond Oil, Inc. Phone:

Were: Ordered 300 sxs 60/40 pozmix - 10% gel with 500# hulls. 5 1/2" at 3813' w/125 sxs.
Perforated at 950' - 1760' - 2145'. 8 5/8" at 123' w/125 sxs.
PBTB 3564'. Dakota 663' - 918'. Anhy. 1748' - 1788'. Salt 2048' - 2098'.

RECEIVED
KANSAS CORP COM
OCT 20 1:36 PM

10-20-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:00 P.M., Day: 14, Month: October, Year: 1997

Actual plugging report: Ran tubing to 3550'. Allied pumped 12 sxs gel w/100# hulls.
Followed with 30 sxs 60/40 pozmix - 10% gel w/100# hulls. Pulled to 2,200' - pumped 75 sxs
cement with 100# hulls. Pulled to 1100' - pumped 65 sxs w/100# hulls. Cement circulated.
PTOH. Squeezed with 35 sxs - Max. P.S.I. 500#. S.I.P. 200#. Pumped 60 sxs down 8 5/8"
w/100# hulls. Max. P.S.I. 200#. S.I.P. 100#.

Remarks: Emergency order to plug with rig over hole.

Condition of casing(in hole): GOOD BAD X
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING

Anhy plug: YES X NO
Dakota plug: YES X NO
Elevation: 2290 GL

I did [X] / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE OCT 23 1997

INV. NO. 49253

10-14