

6-19

4-041687

API Number: 15-065-20,597 -0000

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE NE SE/4 SEC. 10, 09 S, 21 W
2310 feet from S section line
330 feet from E section line

Operator license# 5229

Lease: Loveridge Well # 6

Operator: Phillips Petroleum Company

County: Graham 124.09

Address: 510 N. 3rd Street
Plainville, Kansas 67663

Well total depth 3818 feet
Conductor Pipe: 0 inch @ 0 ft
Surface pipe 8 5/8" Inch @ 267 ft
w/175 sxs.

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Halliburton Cementing License# _____

Address: Hays, Kansas 67601

Company to plug at: Hour: 10:00A.M. Day: 19 Month: June Year: 1995

Plugging proposal received from: Dave Stahl

Company: Phillips Petroleum Company Phone: _____

Were: 5 1/2" casing set at 3817' w/400 sxs. cement. Perf. at 3404' - 3770'. Dakota at 960'. Holes in casing and squeezed at 1411' - 1441' and 2017' - 2048' squeeze with 750 sxs cement.

Ordered 325 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 1:30 P.M., Day: 19, Month: June, Year: 1995

Actual plugging report: R.I.H. with tubing to 3330'. Spotted 70 sxs cement with 100# hulls. Pulled to 2314' - spotted 70 sxs cement with 100# hulls. Pulled to 1300' - spotted 102 sxs cement to circulate at surface. Pulled tubing and squeezed casing with 30 sxs cement and 50# hulls. Max. P.S.I. 500#. S.I.P. 200#. Squeezed 8 5/8" annulus surface pipe with 55 sxs cement and 100# hulls. Max. P.S.I. 300#. Job completed.

Remarks:

Condition of casing(in hole): GOOD _____ BAD X Anhy.plug: YES X NO _____

Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING X, CASING _____, Elevation: _____ GL _____

I did[X] / did not[] observe the plugging.

Dennis J. Hamel
(agent)

INVOICED

DATE 7-26-95

INTL. NO. 43167

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1995

Form CP-2/395
CONSERVATION DIVISION
WICHITA, KANSAS

7-21-95