

4-032063

6-6 15-065-20616-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

API number: 15- -  
NW SE SW /4 SEC. 10 18, 09 S, 21 W  
990 feet from S section line  
3630 feet from E section line

Operator license# 5229

E. McCZAP  
Lease Clack well # 3

Operator: Phillips Petroleum

County Graham 12236

Address: 510 NW Third Street  
Plainville, Kansas 67663

Well total depth 3765 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 261 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Paradise Flats Well Service License# 3240

Address: Paradise, Kansas 67658

Company to plug at: Hour: A.M. Day: 6 Month: June Year: 95

Plugging proposal received from: Dave Stahl

Company: Phillips Petroleum Phone: 6-13-95

Were: Order 350 sxs. 60/40 pozmix - 10% gel.  
4 shots at 960' critical area control.  
Order workstring 2 7/8" tubing.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 13 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]  
Completed: Hour: 11:45A.M., Day: 6, Month: June, Year: 95

Actual plugging report: 8 5/8" set at 261' w/200 sxs. 5 1/2" set at 3764'  
w/450 sxs. T.O.C. 1950. Squeezed at 1803' - 1834' w/100 sxs. 1191' - 1220'  
w/350 sxs. Ran work string to 3324'. Mixed and pumped down 2 7/8" 70 sxs.  
cement blend to 2343'. Pulled to 2343', mixed and pumped 70 sxs. cement  
blend to 1337'. Pulled pipe to 1337' to circulate with 90 sxs. cement blend.  
Pulled work sting. Squeezed 5 1/2" with total 245 sxs. cement blend to Max.  
P.S.I. 300#. Close in S.I.P. 300#. Squeezed 8 5/8" with 10 sxs. cement  
blend to Max. P.S.I. 300#. Close in P.S.I. 300#. Plug complete.

Remarks:  
Condition of casing(in hole):GOOD     BAD     Anhy.plug:YES 1618 NO      
Bottom plug(in place):YES    , CALC    , NO     Dakota plug:YES X, NO      
Plugged through TUBING    , CASING    . Elevation:     GL

I did[ X ] / did not[     ] observe the plugging. Carl Goodrow  
(agent)

**INVOICED**  
DATE 6-23-95  
INV. NO. 42992

FD