

6 040854

2-2-88

API NUMBER 15-065-22418-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

110' W E/2 E/2 SEC. 10, T 9 S, R 21 W/E
NW NW

_____ feet from S section line

_____ feet from E section line

Lease Name Gossebin Well # 1-10

County Graham 123.18

Well Total Depth 3790 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300' w/190 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number _____

Address Chase, Ks.

Company to plug at: Hour: 9:00AM Day: 2 Month: Feb Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) _____

were: 5 1/2" at 3787' w/150 sks; Top perf 3722' - 3671'; P.B.T.D. 3700';

Plug bottom sand to 3625' and 5 sks cement on sand. Shot at 2700' and rec same.

Order 250 sks 65/35 Poz 10% Gel w/2% Lite w/1/4# F.C. plus 8 sks Hulls.

_____ Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:00AM Day: 2 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 8 5/8" S.P. 50 sks cement w/1/4# F.C. plus 200 sks
cement w/1/4# F.C. w/8 sks Hulls mixed in cement. Max Psi 500# Shut in 300#.

RECEIVED
STATE CORPORATION COMMISSION

2-12-88 FEB 12 1988

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Witnessed part of this plugging Gilbert P. Leiker and Gilbert Balthazor.
(If additional description is necessary, use BACK of this form.)

INV. NO. 19851 observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis L. Hamel

LR

DATE 2-15-88
INV. NO. 19851