

9-30-87 15-065-01492-00-00

6 030962

API NUMBER 15- 1943

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SW
SEC. 24, T 9 S, R 21 W/E

990 feet from S section line

4950 feet from E section line

Lease Name ^{Flora kcc 24r} Barry Well # 1

County Graham 122.72

Well Total Depth 3776 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 275

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Operator: Murfin Drilling Co.
Name & Address 250 North Water Suite 300
Wichita, Kansas 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Hays, Kansas

Company to plug at: Hour: AM Day: 30 Month: Sept Year: 19 87

Plugging proposal received from John Turner

(company name) Murfin (phone)

were: 10 3/4" set at 275' w/100 sks. 5 1/2" set at 3769' w/250 sks PBDT 3752'.

Perf 3441' - 3743'. Squeezed at 1057' - 1375' w/310 sks and 74' w/75/sks cwc.

Order 200 sks 65/35 Pozmix 10% Gel 2% Dical Econolite Cement Blend 5 sks Hulls.

Halliburton Cement Company Water truck.

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 AM Day: 30 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Squeezed backside Max Psi 500# cement at surface. Squeeze 5 1/2" casing w/5 sks Hulls in with 200 sks Cement Blend. Max Psi 200#. Close in Psi 150". Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1987

10-23-87

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
(could) observe this plugging.

Signed *Carl Goodrow*
(TECHNICIAN)
Carl Goodrow

DATE 10-26-87

INV. NO. 18669

09-30