

API NUMBER 15-065-21,899-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE-NW-SW, Sec. 25, T 9 S, R 21 WE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2310 feet from N(S) section line

TECHNICIAN'S PLUGGING REPORT 990 feet from W/E section line

Operator License # 6171 Lease Name D. SUTOR Well # 1

Operator: HIGH PLAINS OIL EXPLORATION County GRAHAM

Name & Address HC 39 - BOX 355 Well Total Depth 3823 feet 124.24

HAYS, KS. 67601 Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 260'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor EMPHASIS OIL OPERATIONS License Number 8241

Address P.O BOX 506, RUSSELL, KS. 67665

Company to plug at: Hour: 3:00 AM Day: 16th Month: JAN. Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO RON BURTON

(company name) EMPHASIS OIL OPERATIONS (phone) 913-628-6972

were:  
8 5/8" - 260' SP. CUL #150 COMMON GEL - CA-CL - 2% 3% BY ALLIED CMT.  
ORDER 200 50/50 FORMIX GEL - CA-CL - 2 3% CELLO AND 8 5/8" PLUG  
NO CIRCULATION PROBLEMS - NO SHOW OR BLOW - ELV. 2189 - ANH. 1718  
HEBUCYLE @ 3791'

Signed Marcus Schmidt  
(TECHNICIAN) 801C

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:15 AM Day: 16th Month: JAN. Year: 1984

ACTUAL PLUGGING REPORT

ORDERED 200 50/50 FORMIX GEL - CA-CL - 2 3% CELLO AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN PLUG.

1st PLUG @ 3780' 20' CMT. - 2nd PLUG @ 1740' 20' CMT.

3rd PLUG @ 900' 100' CMT., 4th PLUG @ 270' 40' CMT.

5th PLUG SOLID BRIDGE HULL'S - PLUG @ 40' 10' CMT., 10' IN RMT HOLE (CIRCUMFER)

Remarks: CEMENTED BY ALLIED CMT.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Marcus Schmidt  
(TECHNICIAN) 801C

INVOICED RECEIVED  
STATE CORPORATION COMMISSION  
DATE 1-26-84 JAN 23 1984  
INV. NO. 9260-6 CONSERVATION DIVISION  
Wichita, Kansas