

7-15  
API NUMBER 15- 065-22,372-00-00

To: 6 070573  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION S/2 SW SE, SEC. 15, T 9 S, R 22 W/EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

330 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5068  
Operator: Black Petroleum Co.  
Name & Address: 527 Union Ctr. Bldg.  
Wichita, Kansas 67202  
Thomas E. Black

Lease Name Brown Well # 1  
County Graham 123.18  
Well Total Depth 3790 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Drilling Inc. License Number 1808  
Address Box 506 4th S. Kansas, Russell, Kansas 67665

Company to plug at: Hour: Noon Day: 15 Month: July Year: 19 87

Plugging proposal received from Bsl1 Owen

(company name) Emphasis Drilling Inc. (phone) 316-264-9342

were: 8 5/8" 250 ft. SP cwc w/150 sks 60/40 Poz 6% Gel 2% C.C. By Allied.

Proposal 200 sks 60/40 Poz 6% Gel 3% C. C. 1 sk Flocele, and 8 5/8" plug.

Spot with drill stem, recondition hole, mud between all plugs; No circulation

problems. Elv. 2313, Anh. 1819; Mud 45 Vis; 9.6 Weight and 6.8 water loss;

25 sks at 1830' - 100 sks at 1060', 50 sks at 300' 10 sks at 40'.

15 sks in rat hole (Cir) Plugging Proposal Received by Marion Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 15 PM Day: 15 Month: July Year: 19 87

ACTUAL PLUGGING REPORT Ordered 200 sks 60/40 Pozmix 6% gel; 1 sk Flocele 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem with heavy mud between plugs.

1st plug at 1830' w/25 sks cmt. 2nd plug at 1060' w/100 sk cmt. w/1 sk Flocele.

3rd plug at 300 ft w/50 sk cmt. 4th plug at 40' w/10 sks cmt.

15 sks rat hole (circulate) Cemented by Allied Cmt.

Remarks: 7-30-87 RECEIVED  
(If additional description is necessary use BACK of this form.)  
STATE CORPORATION COMMISSION

INVOICED  
DATE 8-5-87  
INV. NO. 17692

AUG 3 1987  
Signed Marion Schmidt  
(TECHNICIAN)  
Marion J. Schmidt  
CONSERVATION DIVISION  
Wichita, Kansas  
8-3-87  
FORM CP-2/3  
Rev. 01-84