

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20357-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 31-9S-24W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: DREILING - A Well Number: 1
County: GRAHAM Total Vertical Depth: 4110 feet

Operator License No.: 30076
Op Name: A & A PRODUCTION
Address: PO BOX 100
HILL CITY, KS 67642

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 250 160 SX CMT
Production: Size 5.5 feet: 4109 125 SX CMT \$133.58
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/03/2001 2:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Order 8 yards Redi-Mix.
Plugging Method:

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/03/2001 4:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 250' w/160 sxs cwc. 5 1/2" set at 4109' w/125 sxs.
Old squeeze N/A. PBTD 4106'.
Prod Perfs 3917' - 4061'.
Four shots recovered 300' of 5 1/2".
Loaded hole with 10 yards Redi-Mix by yield.
Sanded back to 3860' with 5 sxs common cement on sand with bailer.
Plug complete.

INVOICED

DATE

4-20-01

INV. NO.

2001061689

RECEIVED
STATE CORPORATION COMMISSION

APR 19 2001
04-19-2001
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

THUNDERBIRD DRILLING, INC. #1 DREILING "A" 31-9-24W
 WICHITA, KANSAS NW NW NE
 CONTR L. J. DREILING & SONS CTY GRAHAM
 GEOL BILL IVERSEN FIELD DREIL DISC
 E 2551 KB CM 8/13/70 CARD ISSUED 9/24/70 IP P 61 BOPD + 33% WTR
 LKC 3917-24, 4038-42,
 AND 4057-61

API 15-065-20,357

LOG	TOPS	DEPTH	DATUM
* ANHY		2198	+ 353
HEEB		3837	-1286
TOR		3861	-1310
LKC		3874	-1323
BKC		4104	-1553
LTD		4110	-1559
RTD		4110	-1559
* DRILLERS	TOP		

8 5/8" 250/160SX; 5 1/2" 4110
 DST(1) 3873-90/15", 20'VSOCM, BHP 1045-978#, FP 22-44#
 DST(2) 3897-5920/1', 60'GIP, 105'0 & GCM, 425'HO & GCM, 180'WTRY OIL, 1530'SW, BHP 1146-1135#, FP 290-978#
 DST(3) 3925-45/15", 5'M, BHP 44-33#, FP 22-22#
 DST(4) 3996-4020/1', 160'M W/F SP O, BHP 1157-934#, FP 22-89#
 DST(5) 4026-45/1', 5'M, ALL PRESS O#
 DST(6) 4040-68/1', 60'M W/F SP O, BHP 201-111#, FP 56-56#
 DST(7) 4066-85/1', 420'GIP, 40'M, BHP 33-11#, FP 22-22#
 CO & PF 16/4057-61, A250 PLUS 750 SUPER X AC SWB 180 & AC WTR PH(50%OIL), PF 16/4038-42, BP 4050 A250 FU 560'FL/12HRS(200'OIL, REST WTR) SWB 180PH PLUS
 (OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS