

4-031683

4-13

18
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-20,371-00-00

SE NW NE /4 SEC. 31, 09 S, 24 W
4290 feet from S section line
2310 feet from E section line

Operator license# 5131

Lease Dreiling well # A-2

Operator: Thunderbird Drilling, Inc.

County Graham

Address: Box 97
Ellinwood, Kansas 67526

Well total depth 4120 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

133.90

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Great Bend Casing Pullers, Inc. License# 4635 CP

Address: Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 13 Month: April Year: 92

Plugging proposal received from: Gary Burke

Company: Great Bend Casing Pullers, Inc. Phone: _____

Were: Ordered sand and common cement.
Ordered 250 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Allied Cement Company. Hole open by bailer.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 2:00P.M., Day: 13, Month: April, Year: 92

Actual plugging report: Sand back to 3795' w/ 5 sx. common cement on
sand with bailer. Shot @ 2000'. Ran rate good. Couldn't pull. Shot
@ 1204' - tight pump, Cement Blend slurry to 2000'. Pipe came loose.
Laid down casing. Squeezed 8 5/8" with total 250 sx. cement blend w/500#
hulls mixed in to Max. P.S.I. 300#. Close in 200#. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES CALC , NO Dakota plug: YES NO
Plugged through TUBING _____, CASING _____. Elevation: _____ GL _____

I did / did not [] observe the plugging.

Carl Goodrow

DATE 5-18-92

(agent)

INV. NO. 35262

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1992
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

HTD