

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20380-00-00
Spot: CNWNENE Sec/Twnshp/Rge: 31-9S-24W
4950 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: DREILING -A Well Number: 3
County: GRAHAM Total Vertical Depth: 4124 feet

Operator License No.: 30076
Op Name: A & A PRODUCTION
Address: PO BOX 100
HILL CITY, KS 67642

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 266 160 SX CMT
Production: Size 5.5 feet: 4123 125 SX CMT *134.03*
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/09/2001 12:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (785) 421-6266

Proposed Plugging Method: Order 8 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/09/2001 1:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 266' w/160 sxs cwc. 5 1/2" set at 4123' w/125 sxs.
PBSD 4104'. Prod Perf 4053' - 4097'.
4 shots recovered 300' of 5 1/2" casing. Casing may have been squeezed.
Sanded back to 4000' w/5 sxs common cement on sand with bailer.
Load hole with 10 yards Redi-Mix by yield.
Plug complete.

INVOICED

DATE

4-20-01

INVOICE NO.

2001061689

RECEIVED
STATE CORPORATION COMMISSION
04-19-2001
APR 19 2001

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

CONSERVATION DIVISION
130 SOUTH MARKET

THUNDERBIRD DRILLING, INC. #3 DREILING "A" 31-9-24W
 WICHITA, KANSAS NW NE NE

CONTR L. J. DREILING & SONS CTY GRAHAM

GEOL BILL IVERSEN FIELD DREIL

E 2565 KB CM 10/17/70 ^{CARD} ISSUED 12/10/70 IP P 52 BOPD N/W
 LKC 4091-97, 4053-57
 3933-37

API 15-065-20,380

LOG TOPS	DEPTH	DATUM	
			8 5/8" 266/160SX; 5 1/2" 4123 1/2/150SX
* ANHY	2225	+ 340	DST(1) 3929-45/75", 1500' GIP, 960' OIL (GR 41), 60' W, BHP, 951-916#/30", FP 54-302
* B ANHY	2265	+ 300	DST(2) 4016-44/45", 10' M, BHP 82-64#/30", FP 36-45#
HEEB	3855	-1290	
TOR	3878	-1313	DST(3) 4044-82/105", 30' SOCM, 60' HOCM, BHP 695-283#/30", FP 36-54#
LKC	3891	-1326	
BKC	4120	-1555	
LTD	4124	-1559	MICT, PF 4191-97 A500, SWB LD & SWB 1 BOPH/2HRS, PF 4053-57 A500 SWB LD & SWB 2BOPH/2HRS, PF 3933-37 HFW SQZ RE-PERF 3933-37 250MA SWB LD & SWB 2.34BOPH/2HRS A1000 CRA SWB LD & SWB 3BOPH N/W PULL PLUGS SWB 7BOPH, POP
* SMP TOPS			

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS