

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20467-00-00  
Spot: N2NENW Sec/Twnshp/Rge: 31-9S-24W  
4950 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: REIDEL Well Number: 1  
County: GRAHAM Total Vertical Depth: 4110 feet

Operator License No.: 30076  
Op Name: A & A PRODUCTION  
Address: PO BOX 100  
HILL CITY, KS 67642

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.62 feet: 210 175 SX CMT #  
Production: Size 4.5 feet: 2107 175 SX CMT **133.58**  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/03/2001 3:00 PM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix.  
Pull casing:

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/03/2001 5:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 210' w/175 sxs cwc. 4 1/2" set at 2107' w/175 sxs.  
Prod Perfs 3833' - 4071'.  
Sanded back to 3780' w/5 sxs common cement on sand with bailer.  
Three shots recovered 1000' of 4 1/2" casing.  
Loaded hole with 10 yards Redi-Mix by yield.  
Plug complete.

**INVOICED**  
DATE 4-20-01  
INV. NO. 2001061689

RECEIVED  
STATE CORPORATION COMMISSION  
04-19-2001  
APR 19 2001

Remarks:

Plugged through: CSG

CONSERVATION DIVISION  
Wichita, Kansas

District: 04

Signed Carl Goodrow  
(TECHNICIAN)

APR 11 2001

DREILING OIL, INC. #1 REIDEL 31-9-24W  
 VICTORIA, KANSAS N/2 NE NW  
 CONTR DREILING OIL, INC. CTY GRAHAM

GEOL HANS HANSEN FIELD DREIL

E 2525 KB CM 7/4/71 CARD ISSUED 8/5/71 IP P 65 BOPD + 20% WTR  
 LANS 4013-71  
 GR 39


API 15-065-20,467

LOG	TOPS	DEPTH	DATUM	
*SC		2180	+ 345	8 5/8" 240/175sx; 4 1/2" 4107/175sx
*B SC		2215	+ 310	DST(1) 3821-44/1', 10'M, BHP 1313-548#/ 30", FP 30-30#
TOP		3584	-1059	DST(2) 3842-72/1', 60'SOCM, BHP 1052-985 FP 48-70#
HEEB		3812	-1287	DST(3) 3888-3924/1', 15'M, BHP 387-362# /30", FP 36-36#
TOR		3835	-1310	DST(4) 3909-42/1', 300'GIP, 240'OCM 300'WCO, 540'OILY WTR, BHP 864-840# /30", FP 88-532#
LANS		3849	-1324	DST(5) 3960-4020/1', 300'SOCMW, BHP 1322- 1273#, FP 78-187#
BKC		4080	-1555	MICT, PF 6/4068-71, 6/4032-35, 6/4013- 16 4000 ACID SWB LD & SWB 20BFPH 75%OIL POP
ID		4110	-1585	
*DRILLERS	TOPS			

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS