


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 29 Twp. 9S Rge. 25 (~~EXXXX~~) (W)
Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner Leben Drilling Company
Lease Name Rohleder Well No. 1
Office Address 905 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 23, 1961 19
Application for plugging filed November 23, 1961 19
Application for plugging approved November 23, 1961 19
Plugging commenced November 23, 1961 19
Plugging completed November 23, 1961 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4120 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Sand-Shale	0	222	8 5/8"	210	=0=

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 540' with 20 sacks cement.
Plug set at 180' with 20 sacks cement.
Plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 1961
12-07-1961
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 4th Nat'l Bk. Bldg., Wichita 2, Kansas
(Address)

Subscribed and sworn to before me this 30th day of November, 1961

My commission expires October 21, 1962.
Lucille H. Harr
Lucille H. Harr Notary Public.



LOG

COMPANY: Leben Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Rohleder # 1
 LOCATION: C SW SE of Section 29-9S-25W, Graham County, Kansas
 COMMENCED: November 13, 1961 ELEVATION: 2599 KB
 COMPLETED: November 23, 1961 POTENTIAL: D & A

0	to	222	Surface Sand-Shale
222	to	1520	Shale-Sand-Shells
1520	to	1798	Shale-Shells
1798	to	2011	Sand
2011	to	2240	Shale-Shells
2240	to	2278	Anhydrite
2278	to	2740	Shale-Shells
2740	to	2870	Shale
2870	to	3891	Shale-Lime
3891	to	3935	Lime
3935	to	4040	Lime-Shale
4040	to	4120	Lime
4120			Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 7 1961
 CONSERVATION DIVISION
 Wichita, Kansas


SET: 210' of 8 5/8" casing with 225 sacks cement.

SAMPLE TOPS:

Anhydrite	2240	+ 359
Heebner	3846	-1247
Toronto	3868	-1269
Lansing KC	3881	-1282
Rotary Total Depth	4120	

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Rohleder # 1, C SW SE of Section 29-9S-25W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.


 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 30th day of November, 1961.


 Lucille H. Harr, Notary Public

