

15-065-19113-00-00


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

GRAHAM County, Sec. 29 Twp. 9 Rge. 25 (W)

Location as "NE/CNW%SW%" or footage from lines NE SE SE
Lease Owner BANKOFF OIL CO.
Lease Name ROHLER Well No. 1
Office Address P. O. DRAWER 2479, TULSA, OKLAHOMA
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed SEPTEMBER 26 19 62
Application for plugging filed SEPTEMBER 26 19 62
Application for plugging approved SEPTEMBER 26 19 62
Plugging commenced SEPTEMBER 26 19 62
Plugging completed SEPTEMBER 26 19 62
Reason for abandonment of well or producing formation DRY HOLE.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY, HAYS, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4050 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	211'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

BOTTOM PLUG @ 550' W/15 SACKS CEMENT
2ND PLUG @ 200' W/10 SACKS CEMENT
TOP PLUG @ 40' TO SURFACE W/10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1962
11-13-1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor CHEMICAL & TECHNICAL SERVICES, INC.
Address BOX D., HILL CITY, KANSAS

STATE OF KANSAS COUNTY OF GRAHAM, ss.
DANIEL F. MCCARTHY (employee ~~or owner~~ or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Daniel F. McCarthy
BOX D., HILL CITY, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of November, 19 62
Danald Law
Notary Public.

My commission expires _____ My commission expires May 25, 1964

15-0 65-19113-00-00

CONTRACTOR'S WELL LOG

CONTRACTOR: CHEM-TECH
 OWNER: LEBEN & BANKOFF
 WELL: ROHLER #1
 LOCATION: NE NE SE
 SEC. 29-9S-25W
 GRAHAM CO, KANSAS
 COMMENCED: 9/18/62
 COMPLETED: 9/26/62

0	185	CLAY & SAND	ELEVATION: KELLY BUSHING	2561'
185	211	BLUE SHALE	DERRICK FLOOR	2559'
211	540	SHALE	GROUND LEVEL	2554'
540	1400	SHALE & SAND		
1400	1664	SHALE & RED BED		
1664	1790	SHALE, SHELLS & RED BED		
1790	1975	SAND		
1975	2201	SHALE		
2201	2238	ANHYDRITE		
2238	2445	SHALE & SHELLS		
2445	2840	SHALE, SHELLS & LIME		
2840	3832	LIME & SHALE		
3832	3890	LIME		
3890	3960	LIME & SHALE		
3960	4050	LIME		
4050		ROTARY TOTAL DEPTH		

RECEIVED
 WATER REGULATION COMMISSION
 OCT 1 1962
 CONSERVATION DIVISION
 Wichita, Kansas

SET 211' 7" SURFACE CASING W/90 SACKS CEMENT

DRY & ABANDONED

WE HEREBY CERTIFY THIS TO BE A CORRECT AND ACCURATE LOG OF THE ABOVE MENTIONED WELL,
 AS SHOWN ON THE DAILY DRILLING REPORTS.

CHEMICAL & TECHNICAL SERVICES, INC.

BY: *D. F. McLeath*
 ASST. TREASURER

SUBSCRIBED AND SWORN TO BEFORE THIS 27th DAY OF SEPTEMBER, 1962.

Notary Public Expires January 23, 1965

Conrad Mueller
 NOTARY PUBLIC