


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-065 - 00652-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County. Sec. 30 Twp. 9 Rge. 25 (E) (W)

Location as "NE/CNW/SW" or footage from lines C of NW SE
Lease Owner Imperial Oil of Kansas
Lease Name Richmeier Well No. #1
Office Address Wakeeney, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed 9-8-61 19
Application for plugging approved 19
Plugging commenced 9-13-61 19
Plugging completed 9-15-61 19
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4083 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 4000'. Mixed and run 3 sacks cement with dump bailer.
Pulled casing. Circulated casing with 16 sacks gel and spotted 20 sacks cement at 550'. Pulled casing and spotted 20 sacks cement at 170'. Pulled balance of pipe. Mudded to 140' and sat 10' rock bridge with 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1961
09-19-1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18 day of Sept., 19 61

24 October 1964

Sidney D. Miller
Notary Public.



DRILLER'S LOG

15-065-00652-00-00

Imperial Oil Company
780 Fourth National Building
Wichita 2, Kansas

Richmeier No. 1
C NW SE Sec. 30-9S-25W
Graham County, Kansas

Total Depth: 4400'

Elevation: 2604 RB
Production:

Commenced: 6-8-61 Completed: 6-20-61

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 189' with 150 sacks cement.
Set 4-1/2" production pipe at 4083 with 100 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	<u>Elec. Log</u>
Surface Clay & Sand	189'	Heebner	3843 (-1239)
Shale & Sand	1790'	Toronto	3863 (-1259)
Dakota Sand	2000'	Lansing	3876 (-1272)
Shale & Red Bed	2040'	B/Kansas City	4107 (-1503)
Shale & Shells	2240'	Marmaton	4136 (-1532)
Anhydrite	2274'	Cherokee Shale	4328 (-1724)
Shale & Shells	2320'	Cherokee Lime	4340 (-1736)
Shale & Lime	2700'	Total Depth	4400 (-1796)
Shale & Shells	2895'		
Shale & Lime	3712'		
Lime	4400'		
Rotary Total Depth	4400'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

RECEIVED
STATE CORPORATION COMMISSION

OCT 5 1961

CONSERVATION DIVISION
Wichita, Kansas

IMPERIAL OIL COMPANY

By Raymond L. Bacon
Raymond L. Bacon

Subscribed and sworn to before me this 23rd day of June, 1961.

My Commission Expires:



Bette J. Behymer
Bette J. Behymer, Notary Public