

15-065-20489-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Graham County, Sec. 30 Twp. 9S Rge. (E) 25 (W)

Location as "NE/CNW%SW%" or footage from lines NE SW NW  
Lease Owner Abercrombie Drilling, Inc.  
Lease Name WERTH Well No. 1  
Office Address 801 Union Center, Wichita, Ks. 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed September 26, 19 71  
Application for plugging filed September 26, 19 71  
Application for plugging approved September 26, 19 71  
Plugging commenced September 26, 19 71  
Plugging completed September 26, 19 71  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation Depth to top Bottom Total Depth of Well 4157 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	235'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug set at 1280' w/50 sx.  
2nd plug set at 240' w/20 sx.  
Top plug set at 40' w/10 sx.  
Job complete at 7:00 a.m. 7-26-71.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas

09-29-1971

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well has been filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1971

My commission expires February 10, 1975

Beverly Mann  
Beverly Mann, Notary Public.



CONTRACTOR'S WELL LOG

15-065-20489-00-00

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	WERTH #1
LOCATION:	NE SW NW, Sec. 30-9S-25W Graham County, Kansas
GEOLOGIST:	Jack K. Wharton
SPUD DATE:	September 18, 1971
COMPLETION DATE:	September 26, 1971

0	50	Clay
50	80	Sand
80	180	Clay & Shale
180	237	Shale
237	1220	Shale & Shells
1220	1300	Shale
1300	1380	Sand
1380	1730	Shale
1730	1866	Shale & Sand Streaks
1866	2044	Sand
2044	2268	Shale (Red Red)
2268	2308	Anhydrite
2308	2970	Shale & Lime
2970	3145	Lime & Shale
3145	4155	Lime
	4155	Rotary Total Depth

Drilled 237' of 12½" surface hole, set 8-5/8" csg. at 235' K.B. w/150 sx. cement. Cement circulated. Plug was down at 4:45 p.m. 9-18-71.  
Dry and Abandoned

ELECTRIC LOG TOPS

ELEVATION

Anhydrite	2276 (+ 351)
B/Anhydrite	2310 (+ 317)
Heebner	3865 (-1238)
Toronto	3887 (-1260)
Lansing	3900 (-1273)
Base/K.C.	4134 (-1507)
ELTD	4158 (-1531)

2627 K.B.
2625 D.F.
2519 G.L.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS        )  
                                  ) SS  
COUNTY OF SEDGWICK    )

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WERTH #1, NE SW NW, Sec. 30-9S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
Jerry A. Langrehr

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 27th day of September, 1971.

Beverly Mann  
Beverly Mann, Notary Public

