

15-065-21318-00-00

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County. Sec. 30 Twp. 9S Rge. 25 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
NW SW

Lease Owner F & M Oil Company

Lease Name WERTH "A" Well No. 1

Office Address 422 Union Center, Wichita, Kansas 67202

Character of Well (Completed as Oil, Gas or Dry Hole) _____

Dry Hole

Date Well completed 10-14 1980

Application for plugging filed 10-14 1980

Application for plugging approved 10-14 1980

Plugging commenced 10-14 1980

Plugging completed 10-14 1980

Reason for abandonment of well or producing formation _____

No commercial quantity of oil or gas available

If a producing well is abandoned, date of last production _____


19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4134'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 4134'.

Set 1st plug @ 1200' with 70 sx.

2nd plug @ 260' with 20 sx.

3rd plug @ 40' solid bridge with 10 sx.

Rathole with 5 sx. 50/50 posmix, 6% gel

Plug was down @ 11:45 p.m. 10-14-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 80

Jeanette A. Metheny
Jeanette A. Metheny Notary Public.

My commission expires 08-18-84



RECEIVED
STATE CORPORATION COMMISSION
NOV - 7 1980
11-07-1980
CONSERVATION DIVISION
Wichita, Kansas

15-065-21318-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	F & M Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	WERTH "A" #1
LOCATION:	NW SW, Section 30-9S-25W Graham County, Kansas
SPUD DATE:	10-09-80
COMPLETION DATE:	10-14-80

0	1524	Sand & Shale
1524	1565	Anhydrite
1565	1589	Sand & Shale
1589	4143	Shale & Lime
	4143	RTD

SAMPLE TOPS:

Anhydrite 1524'
B/Anhydrite 1565'

Spud hole @ 12:30 p.m. 10-09-80. Drilled 286' of a 12-1/4" hole. Ran 7 joints of 8-5/8" new 20# casing (tally 277') Set @ 284' K.B. Cemented with 220 sx. common cement, 3% c.c., 2% gel. Plug was down @ 4:00 p.m. 10-09-80.

T.D. 4134'. Set 1st plug @ 1200' with 70 sx. 2nd plug @ 260' with 20 sx. 3rd plug @ 40' solid bridge with 10 sx. Rathole with 5 sx. 50/50 posmix, 6% gel. Plug was down @ 11:45 p.m. 10-14-80.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WERTH "A" #1, NW SW, Section 30-9S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*
Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 5th day of November, 1980.

Jeanette A. Metheny
Jeanette A. Metheny, Notary Public



RECEIVED
STATE CORPORATION COMMISSION

NOV - 7 1980

CONSERVATION DIVISION
Wichita, Kansas