

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 31 Twp. 9S Rge. 25 (E) (W) **X**

Location as "NE/CNW%SW%" or footage from lines NE NE NW

Lease Owner Empire Drilling Company

Lease Name Fred Richmeier Well No. 1

Office Address 650 Fourth National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 24, 1961 19

Application for plugging filed January 24, 1961 19

Application for plugging approved January 24, 1961 19

Plugging commenced January 24, 1961 19

Plugging completed January 24, 1961 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4105 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Sand-Shale	0	192	8 5/8"	179'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 400' with 20 sacks cement.

Plug set at 175' with 20 sacks cement.

Plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 2 1961
02-02-1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company

Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Irwin Kornfeld (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Irwin Kornfeld

650-4th Nat'l. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of February, 1961

Lucille H. Harr
Lucille H. Harr Notary Public.

My Commission expires October 21, 1962



LOG

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Fred Richmeier # 1
 LOCATION: NE NE NW Section 31-9S-25W, Graham County, Kansas
 COMMENCED: January 16, 1961 ELEVATION: 2582 KB
 COMPLETED: January 24, 1961 POTENTIAL: D & A

* * * * *

0	to	192	Sand-Shale
192	to	1770	Shale-Shells
1770	to	2233	Sand-Shale
2233	to	2268	Anhydrite
2268	to	2687	Shale-Shells
2687	to	2855	Shale-Lime
2855	to	3226	Lime-Shale
3226	to	3320	Shale-Lime
3320	to	3440	Lime-Shale
3440	to	3533	Shale
3533	to	3735	Shale-Lime
3735	to	3875	Lime-Shale
3875	to	4105	Lime
4105			Rotary Total Depth

SET: 179* 8 5/8" with 150 sacks cement.

ELECTRIC LOG TOPS:

Heebner	3826	-1244
Toronto	3846	-1264
Lansing	3862	-1280
Base Kansas City	4086	-1504

* * * * *

CERTIFICATION

I, Irwin Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Fred Richmeier # 1, NE NE NW Section 31-9S-25W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.

Irwin Kornfeld

 IRWIN KORNFELD

Subscribed and sworn to before me, a Notary Public within and for Sedgwick County, Kansas, this 1st day of February, 1961.

Lucille H. Harr

 LUCILLE H. HARR, Notary Public



STAB.
 FEB 2 1961
 CONSTRUCTION DIVISION
 WICHITA, KANSAS