

15-065-20973-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 31 Twp. 9 Rge. 25 N/W
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines NW SE SE

Lease Owner Liberty Enterprises, Inc.
Lease Name Brumgardt #1 Well No. #1
Office Address 308 W. Mill
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

DRY HOLE
Date Well completed November 29 1977
Application for plugging filed November 29 1977
Application for plugging approved November 29 1977
Plugging commenced November 29 1977
Plugging completed November 29 1977
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well _____
Producing formation NONE Depth to top _____ Bottom _____ Total Depth of Well 3880'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	208	8 5/8	208	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Mixed 70 Sx at 1020' Mixed 20 Sx at 210'
Mixed 10 Sx at 40'

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1978
01-20-1978
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing, Inc.

STATE OF Kansas COUNTY OF Rooks, ss.
Roger L. Comoau (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Roger L. Comoau
308 W. Mill Plainsville, Mo 67663
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of November, 1977.

My commission expires _____



Krystal Schwenn
Notary Public.

15-05-20973-00-00

DRILLERS LOG

BRUNGARDT #1

CASING RECORD:

8 5/8" set at 208'

TOTAL DEPTH:

3880'

DESCRIPTION:

NW SE SE
Sec. 31-9-25, Graham County, Kansas

OPERATOR: Liberty Enterprises Inc.

CONTRACTOR: Helberg Oil Company

COMMENCED: November 15, 1977

COMPLETED: November 22, 1977

FORMATION	FROM	TO	REMARKS
Sand & Shale	0	200	
Sand & Shale	200	226	
Sand & Shale	226	390	
Sand & Shale	390	1430	
Shale & Sand	1430	1920	
Sand & Shale	1920	2228	
Anhydrite	2228	2270	
Sand & Shale	2270	2510	
Shale	2510	2646	
Shale & Lime	2646	2746	
Shale	2746	2920	
Shale	2920	3028	
Shale	3028	3198	
Shale	3198	3313	
Shale	3313	3445	
Shale	3445	3585	
Shale	3585	3685	
Shale	3685	3780	
Lime	3780	3840	
Shale & Lime	3840	3856	
Lime	3856	3880	
T.D.	3880		D & A

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1978

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

HELBERG OIL COMPANY

Jerry M. Helberg
Jerry M. Helberg

Subscribed and sworn to before me this 30 day of November, 1977.

Faye E. Minium
Faye E. Minium, Notary Public

