

15-065-20028-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 33 Twp. 9S Rge. 25W (E) (W)
Location as "NE/CNW/SW" or footage from lines 110' E. of W $\frac{1}{2}$ W $\frac{1}{2}$ NW
Lease Owner Bankoff & Leben
Lease Name Brungardt Well No. 3
Office Address P. O. Drawer 2479, Tulsa, Okla. 74101
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-7-67 19
Application for plugging filed 4-7-67 19
Application for plugging approved 4-7-67 19
Plugging commenced 4-7-67 19
Plugging completed 4-7-67 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4090 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 540' with 20 sacks cement
Plug @ 210' with 20 sacks cement
Plug @ 40' with 1/2 sk. hulls & 10 sks. cement

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1967
04-11-1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Leben Drilling, Inc.
Address: Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of April, 1967

My commission expires April 1, 1971
Ulanda Nichols
Notary Public.

15-065-20028-00-00

DRILLER'S LOG

COMPANY: Bankoff & Leben
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: BRUNGARDT #3
 LOCATION: 110' E. of W $\frac{1}{2}$ W $\frac{1}{2}$ NW
 SEC. 33-9S-25W
 GRAHAM COUNTY, KANSAS
 COMMENCED: 3-29-67
 COMPLETED: 4-7-67

0	100	Surface Clay, Sand
100	175	Clay, Sand
175	1310	Shale
1310	2050	Shale, Shells
2050	2211	Shale, Redbed
2211	2248	Anhydrite
2248	2290	Shale, Shells
2290	2620	Shale, Shells, Lime
2620	2918	Shale, Lime
2918	3277	Lime, Shale
3277	3430	Shale, Lime
3430	3548	Lime, Shale, Chalk
3548	3800	Lime, Shale
3800	4090	Lime
	<u>4090</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE DEPARTMENT OF GEOLOGY
 APR 11 1967
 CONSERVATION DIVISION
 Wichita, Kansas


8 5/8" 20# new surface casing set @ 211' cemented with 175 sacks
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Brungardt #3 Well, located 110' East of W $\frac{1}{2}$ W $\frac{1}{2}$ NW of Section 33, Township 9 South, Range 25 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, as of this 10th day of April, 1967.



Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971