


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

WELL PLUGGING RECORD

Sheridan County, Sec. 3 Twp. 9S Rge. 26 (W)

Location as "NE/CNW&SW" or footage from lines _____
 Lease Owner Amerada Petroleum Corporation
 Lease Name L. Sheehan Well No. 1
 Office Address P. O. Box 2040, Tulsa 2, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 6-13 19 63
 Application for plugging filed 6-13 19 63
 Application for plugging approved 6-13 19 63
 Plugging commenced 8:45 p.m. 6-13 19 63
 Plugging completed 10:15 p.m. 6-13 19 63
 Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19 _____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4348 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	322'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4348 to 540' Heavy rotary mud
540 to 330' HB plug, 20 sacks cement
330 to 40' HB plug, 20 sacks cement
40 to cellar HB plug, 10 sacks cement, 1/2 sack hulls

RECEIVED
 STATE CORPORATION COMMISSION

JUN 26 1963
06-26-1963
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.
 Address Box 359, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Peel Brothers, Inc. (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Mattocks
W. E. "Jack" Mattocks, Drlg. Supt.
Box 359, Hoisington, Kansas

SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 63

Etzel S. Williamson
 Notary Public.

My commission expires 6-21-66

R
DRILLER'S LOG

Well Owner: Amerada Petroleum Corporation
Farm Name: L. Sheehan #1
Commenced: 6-3-63
Completed: 6-14-63
Total Depth: 4348'
Casing: 8-5/8" set at 334'cem.

Section 3-9S-26W
Sheridan County, Kansas

Elevation:

Production: Dry

Contractor: Peel Brothers, Inc.

Figures below indicate bottoms of formations: .

Clay and Sand	0 - 80
Sand and Shale	1210
Gypsum with Shale	1795
Sand	1970
Shale and Shells	2215
Anhydrite	2254
Shale	2625
Shale and Lime	2965
Lime	4210
Lime and Shale	4280
Conglomerate	4305
Mississippi Lime and Chert	4348
Total Depth	4348

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1963

CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of our knowledge true and correct.

PEEL BROTHERS, INC.

Jack Mattocks
W. E. "Jack" Mattocks
Drilling Superintendent

WEM:e

SUBSCRIBED AND SWORN to before me this 18th day of June, 1963

My commission expires: June 21, 1966

Sheel S. Williamson
Notary Public