

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
RECEIVED
6-4-68
STATE CORPORATION COMMISSION

SEP 28 1970
CONSERVATION DIVISION
Wichita, Kansas

09-28-1970
25

15-163-01917-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kewanee Oil Company

Complete Address P. O. Box 360 Hoisington, Kansas 67544

Lease Name Husted "A" Well No. 3

Location NW NW SE Sec. 11 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3605'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 2:15P Day 21 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3605' 8 5/8 csg set at 1464' cwc 700 sk.

5 1/2 csg set at 3603' cw 200 sk cmt.

~~Filled 5 1/2 csg W/sd (3580-3605) Dumped 5' sk cmt W/dump-bailer. (3540-3580)~~

Recovered 2515' of 5 1/2 csg.

Filled 8 1/2 5/8 csg W/mud to 700' -set 20' rock and 3 yds readymix cmt. (480-700)

Mud to 235' set 20' rock and 3 yds readymix cmt. (0-235)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 9-28-70

INV. NO. 2590-W