

KANSAS

J
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20096-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1968
CONSERVATION DIVISION
Wichita, Kansas
03-29-1968

Operator's Full Name Murfin Drilling Company

Complete Address: 607 Union Center Wichita, Kansas

Lease Name Winters Well No. 1

Location Approx. SE SW SE Sec. 22 Twp. 10 Rge. 19 (E) (W) X

County Rooks Total Depth 3664

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Co. Tools

Address: _____ License No. _____

Operation Completed: Hour 9:30 P Day 26 Month 3 Year 1968

The Above well was plugged as follows:

RTD 3664' 8 5/8 csg set at 227' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1968
CONSERVATION DIVISION
Wichita, Kansas
04-02-1968

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/29/68

INV. NO. 7494-W

Signed: Geo F. Mansur
Well Plugging Supervisor