

KANSAS

Form CP-3  
Rev. 6-4-68

f

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

DEC 10 1976  
12-10-1976  
CONSERVATION DIVISION  
(of this well)

API Number 15 -163 -20,663-00-00

Operator's Full Name Graves Drilling Co., Inc.

Complete Address 910 Union Center, Wichita, Kansas

Lease Name Collins Well No. 1

Location NE NE NW Sec. 23 Twp. 10 Rge. (E) (W) 19

County \_\_\_\_\_ Rocks: \_\_\_\_\_ Total Depth 3650'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A XX

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 11:50 P Day 6 Month 12 Year 1976

The above well was plugged as follows:

RTD 3650' 8 5/8 csg set 215' cwc 150 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: [Signature]  
Well Plugging Supervisor

DATE 12-10-76

INV. NO. 4300-w