

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-163-04066-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NE NE

SEC. 23 TWP. 10 RGE. 19 *W*

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Catudal

Operator M. B. Armer Drilg. Co. INC. Address 710 Petr. Bldg. Wichita, Kans

Field _____ County Rooks

Total Depth 3605 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 178' circulated with 100 sax - 5 1/2" at 3604 with
125 sax behind. Lane Wells plugs to 3206', top perf., 3170'.
Filled with chat to 3160', set 4 sax cement with dump bailer,
hole circulated with Aquagel and hulls, pulled 1000' 5 1/2",
heavy mud to 178', set rock bridge and 15 sax cement, filled
with mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
04 21 1951
APR 21 1951

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 4-18-51

PLUGGING
FILE SEC 23 T 10 R 19
BOOK PAGE 75 LINE 24