

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
04-28-1969

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20199-00-00

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address: N. 400 Woodlawn Wichita, Kansas

Lease Name Winters Well No. 1

Location NE NW NE Sec. 22 Twp. 10 Rge. 19W (H) (W) 10

County Rooks Total Depth 3719'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Sage Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 8P Day 26 Month 4 Year 1969

The Above well was plugged as follows:

RTD 3719' 8 5/8 csg at 254' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Bruce J. Mansel  
Well Plugging Supervisor

INVOICED  
DATE 4/28/69  
INV. NO. 9663-W