

KANSAS

Form CP-3  
Rev. 6-4-68

*Y* STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20270-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 25 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
11-25-1969

Operator's Full Name Range Oil Co., Inc.

Complete Address 402 Insurance Bldg., Wichita, Kansas

Lease Name Vohs Well No. 1

Location NW SW NW Sec. 24 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3611

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Sage Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 6A Day 22 Month 11 Year 1969

The above well was plugged as follows:

RTD 3611' 8 5/8 csg set at 230' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

INVOICED  
DATE 11/26/69  
INV. NO. 920-W