

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-00787-00-92

File No. _____ County: _____ Rooks _____

Location: N $\frac{1}{2}$ SE SW Sec. 24 Twp. 10 Rge. 19 (E) (W) _____

Name of Field: _____ Total Depth: 3552

I have this date completed supervision of plugging of:

Lease Name: Whisman Well No. 1

Operator's Full Name: Thos H. Allan

Complete Address: 925 Union Center Wichita, Kansas

Plugging Contractor: Southwest Casing Pulling Co

Address: Great Bend, Kansas License No. 399

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 20 Month 12 Year 60

The above well was plugged as follows:

8 5/8" 202' circulated with cement - 5 1/2" 3552' with 125 sax cement - PB to 3489', perforated 3408'.

Filled with sand to 3400', set 4 sax cement with dump bailer, pulled 2800' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550', (33 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 170', displaced 20 sax cement through 5 1/2" at 170', heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Halliburton Co.

Signed: Leon Lee
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

12-28-1960
DEC 28 1960

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

DATE 12/28/60

INV. NO. 24394