

KANSAS

Form CP-3
Rev. 6-26-62

24
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-163-20014-00-00

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1967
04-18-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 300 West Douglas Wichita, Kansas

Lease Name Vohs Well No. 1

Location Approx. NE NW Sec. 24 Twp. 10 Rge. 19 (E) (W) X

County Rooks Total Depth 3267

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Inc.

Address: Wichita, Kansas License No.

Operation Completed: Hour 2:15 Day 19 Month 4 Year 1967

The Above well was plugged as follows:

RTD 3267' 8 5/8 csg set at 209' cwcl75 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 200' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. J. Massey
Well Plugging Supervisor

DATE 4/18/67

INV. NO. 5066-4