

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1968
CONSERVATION DIVISION
Wichita, Kansas
01-24-1968

15-163-20090-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name W. F. Newton

Complete Address P. O. Box 250 Conrae, Texas

Lease Name Steeple Well-No. 1

Location C E/2 W/2 NW/4 Sec. 25 Twp. 10 Rge. 19 (E) (W) X

County Rooks Total Depth 3256

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Woodman- Iannitti Drlg. Co.

Address Hosington, Ks. License No.

Operation Completed: Hour 10:15 P Day 20 Month 1 Year 1968

The above well was plugged as follows:

RTD 3256' 8 5/8 csg set at 203' cwc 140 sc. Cem. Mat. 50-50 Poz cem. W/6% gel.
Gunned pits~~g~~ circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cemnt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Murray
Well Plugging Supervisor

DATE 1/24/68
INV. NO. 7137-W