

DISTRICT CONSERVATION AGENT'S REPORT

*[Handwritten signature]*

TO:

15-163-04073-00-00

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW NE

SEC. 31 TWP. 10 RGE. 19W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Schoenthaler 145 N. Water

Operator Midstates Oil Corp Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3816 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 198' circulated with cement - 5 1/2" at 3815  
with 200 sax cement behind - Beker plugs to 3520 - topm  
perforations at 3513'.

Filled with sand to 3495', set 4 sax cement with dump bailer  
pulled 827& 5 1/2", filled hole with mud to 198', set rock  
and 15 sax cement, mud to 35', set rock and 10 sax cement  
to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
66-26-1952  
JUL 26 1952

*[Handwritten signature]*  
District Conservation Agent

Date 7-22-52

PLUGGING  
FILE SEC 31 T (OR 19)  
BOOK PAGE 26 LINE 14

CONSERVATION DIVISION  
Wichita, Kansas