

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

15-103-00292-00-00

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE NW

SEC. 31 TWP. 10 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Schoenthaler

Operator Lohmann - Johnson <sup>Daly, Co. Inc.</sup> Address Evansville, Ind

Field \_\_\_\_\_ County Rooks

Total Depth 3756 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 210' circulated with cement- 5 1/2" at 3755'  
with 80 sax cement behind - Lane Wells plugs to ~~3525~~ 3525  
top perforations at 3480'.

Filled with chat to 3470', set 4 sax cement with dump  
bailer - pulled 3200' 5 1/2" - filled hole with mud to  
200', set rock and 15 sax cement - mud to 35', set rock  
and 10 sax cement to bottom cellar.

**PLUGGING RECEIVED**  
FILE SEC-31 T-10 R-19  
BOOK PAGE 19 LINE 28

STATE CORPORATION COMMISSION  
MAY 29 1952  
05-29-1952  
CONSERVATION DIVISION  
Wichita, Kansas

*[Signature]*  
District Conservation Agent  
Date 5-26-52

*[Signature]*