

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 19 1975  
08-19-1975  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20574-00-00

Dear Sir:

Mr. Moore of C & G Drlg. has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dane G. Hansen Trust

Complete Address: Box 187, Logan, Kansas

Lease Name: Holmes Well No. 4

Location: SE SE NW Sec. 6 Twp. 10 Rge. (E)(W) 20

County: Rooks Total Depth 3874' Oil Well

Gas Well Input Well SWD Well D & A. XX Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 660' thru drill  
pipe. Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud  
to 40' set solid bridge & 10 sk cmt plug to base pf cellar.

Very truly yours,

Red Messing  
Conservation Division Agent