



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-163-20224-00-00

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Teall Well No. A-1

Location: NE-NW-SE Sec. 17 Twp. 10 Rge. (E)(W) 20

County: Rooks Total Depth 3570' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

179'---8 5/8" Surface casing, cement circulated with 160 Sx.

Circulate hole with heavy mud. Pull DP to 875' and displace 100 Sx. cement thru DP. Pull DP to 185' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 1 1969
 07-01-1969
 CONSERVATION DIVISION
 Wichita, Kansas

Very truly yours,

Conservation Division Agent