

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 7 1969

CONSERVATION DIVISION
Wichita, Kansas

01-07-1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-163-20163-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Kohlrus of Sage Drlg. has this date requested permission to plug the following described well:

Mr. Kohlrus guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drlg. Inc.

Complete Address: 400 N. Woodlawn Wichita, Ks.

Lease Name: Romine Well No. 1

Location: NW NE SE Sec. 19 Twp. 10 Rge. 20 (E) (W) X

County: Rooks Total Depth 3747 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Kohlrus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace

70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

Leo F. Murray
Conservation Division Agent