

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Graham County, Sec. 2 Twp. 9 Rge. 24 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW SW

Lease Owner Honaker-Davis Drig. Co.

Lease Name Wagner Well No. 1

Office Address 2008 Lakin, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-7 19 56

Application for plugging filed 9-7 19 56

Application for plugging approved 9-7 19 56

Plugging commenced 9-7 6:00 p.m. 19 56

Plugging completed 9-7 7:30 p.m. 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Milton Galvert

Producing formation Depth to top Bottom Total Depth of Well 4010 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 200' with heavy rotary mud. Dumped in 1/2 sack hulls. Set Plug. Mixed 15 sacks cement by hand and poured in through drill pipe.

Filled hole to 40' with heavy rotary mud. Dumped in 1/2 sack hulls-set plug. Mixed 10 sacks cement by hand and filled hole to bottom of cellar with cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker-Davis Drig. Co.

Address 2008 Lakin, Great Bend, Kansas



STATE OF Kansas, COUNTY OF Barton, ss.
S. C. Lingreen (employee of owner) or (XXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. C. Lingreen
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 56

My commission expires 6-25-59

Kenneth G. Fischer, Notary Public.



09-11-1956

15-065-02153-00-00

DRILLERS LOG

Wagner No. 1
Loc: S1/4, S1/4
Sec: 2-9S-24W
Graham County, Kansas
Company: Monaker-Davis Drilling Co., et al
Contractor: Monaker-Davis Drilling Co.

Comm: 8-25-56
Comp: 9-6-56
Rotary Total Depth: 4010'
Casing: 8-5/8" at 209'
D & A

0	40	Sand	
40	211	Sand & Shale	
211	600	Shale	8-5/8" casing cemented at
600	1350	Shale & Shells	209' with 175 sacks cement
1350	2105	Shale, Shells & Sand	and 4 sacks calcium chloride
2105	2140	Anhydrite	
2140	2510	Shale & Shells	
2510	3765	Line & Shale	
3765	3800	Line	
3800	3840	Line & Shale	
3840	3920	Line	
3920	3940	Line & Shale	
3940	4010	Line	
4010		Rotary Total Depth	D & A

I certify that this is the true and correct copy of the above log to the best of my knowledge.

H. C. Davis
H. C. Davis

Subscribed and sworn to before me this 10th day of September, 1956.

Kenneth G. Fischer
Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING
FILE SEC. 2 T 9 R24W
BOOK PAGE 97 LINE 29