


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 2 Twp. 9 S Rge. 24 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW SW NE

Lease Owner Moble C. Hoover
Lease Name Wilma Harvey Well No. 1
Office Address 302 NBC Building, El Dorado, Arkansas 71730
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry hole



Locate well correctly on above
Section Plat

Date Well completed Oct. 7 1978
Application for plugging filed (verbally) Oct. 7 1978
Application for plugging approved (verbally) Oct. 7 1978
Plugging commenced Oct. 7 1978
Plugging completed Oct. 7 1978
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3965'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to _____
feet for each plug set.

Set 1st plug at 1100' with 70 sacks
2nd plug at 240' with 20 sacks
40' solid bridge with 10 sacks
2 sacks in rathole
Cemented

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1978
10-13-1978
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jack L. Partridge, Ass't. Sec.-Treas. (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 78



Sandra Richman
Sandra Richman Notary Public.

My commission expires July 21, 1979

OPERATOR: Moble C. Hoover
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Wilma Harvey #1
 LOCATION: NW SW NE Section 2-9S-24W
 Graham County, Kansas
 SPUD DATE: September 28, 1978
 COMPLETION DATE: October 7, 1978

0	220	Shale & sand
220	259	Shale
259	900	Sand & shale
900	1152	Shale & sand
1152	1748	Shale
1748	2070	Shale & sand
2070	2074	Sand & shale
2074	2113	Anhydrite
2113	2490	Sand & shale
2490	3396	Shale & lime
3396	3717	Lime & shale
3717	3792	Lime
3792	3868	Lime & shale
3868	3922	Lime
3922	3965	Lime & shale
	3965	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 13 1978
 CONSERVATION DIVISION
 Wichita, Kansas

SAMPLE TOPS:

Anhydrite 2074'
 B/Anhydrite 2113'

Spud hole at 1:45 p.m., September 28, 1978. Drilled 259' of 12 1/4" hole. Ran 6 joints of 8-5/8" - 28# surface casing. Set at 258' K.B. with 185 sacks common cement, 3% CaCl, 2% gel. Cement did circulate. Plug was down at 6:00 p.m., September 28, 1978.

T.D. 3965'. Set first plug at 1100' with 70 sacks, second plug at 240' with 20 sacks, 40' solid bridge with 10 sacks, 2 sacks in rathole. Plug was down at 6:00 a.m., October 7, 1978. State Plugger - Gilbert Balthazor.

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Wilma Harvey #1, NW SW NE Section 2-9S-24W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge,
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 11th day of October, 1978.

Sandra Richman
 Sandra Richman, Notary Public



My commission expires July 21, 1979.