

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 3 Twp. 29 Rge. 24 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NE/4 SW/4 SE/4

Lease Owner Empire Drilling Co

Lease Name Empire Drilling Co-Keith Well No. 7

Office Address Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed JANUARY 1, 1956 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced Aug 19 19 57

Plugging completed Aug 21 19 57

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production DEPLETED 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3940 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	SURFACE	0	170'	8 5/8"	170	0
	CASING	0	3933'	5 1/2"	3933	1418.50'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3940 feet to surface. feet for each plug set.

Hole filled with sand from 3940 to 3875; five sacks of cement then placed in hole with dump bailer, thereafter hole filled with mud ~~XXXX~~ to 200 feet; rock bridge installed and twenty sacks of cement poured into hole, and hole mudded to 35 feet; rock bridge installed and hole capped with ten sacks of cement, forming cement plug to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co., Russell, Kansas.

Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, DAN J. KORNFELD, employee of owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]

650 FOURTH NATIONAL BANK BUILDING

(Address)

SUBSCRIBED AND SWORN TO before me this 28TH day of AUGUST, 1957

My commission expires JULY 2, 1958



[Signature]
HAZEL PIERSON, Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
08-30-1957
AUG 30 1957

PLUGGING
FILE SEC 3 T. 9 R24W
BOOK PAGE 40 LINE 42

CONSERVATION DIVISION
Wichita, Kansas

COMPANY: EMPIRE DRILLING COMPANY
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM: IDA KEITH NO 7
 LOCATION: NE SW SE, SECTION 3-9-24, GRAHAM COUNTY, KANSAS
 COMMENCED: JANUARY 1, 1956 ELEVATION: 2432 KB
 COMPLETED: JANUARY 10, 1956

0	TO	194	SURFACE
194	TO	345	SHALE AND SHELLS
345	TO	1285	SHALE AND SAND
1285	TO	2112	SHALE AND SHELLS
2112	TO	2148	ANHYDRITE
2148	TO	2815	SHALE AND SHELLS
2815	TO	3740	SHALE AND LIME
3740	TO	3952	LIME
		3952	RTD

SET: SURFACE AT 160' WITH 115 SACKS CEMENT, 8 5/8"
 RAN: 5 1/4" PIPE 3946' CEMENTED WITH 75 SACKS CEMENT.

TOPS:	ANHYDRITE	2112
	HEEBNER	3722
	TORONTO	3746
	LANSING	3762


I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE IDA KEITH NO 7, NE SW SE, SECTION 3-9-24, GRAHAM COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 28TH DAY OF AUGUST, 1957.

MY COMMISSION EXPIRES JULY 2, 1958

Hazel Peterson
 NOTARY PUBLIC



PLUGGING
 FILE SEC. 3 T. 9 R. 24W
 BOOK PAGE 40 LINE 42