

15-065-19112-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 3 Twp. 9 Rge. 24 (E) (W)

Location as "NE/CNWKSWK" or footage from lines NE - SW - SW

Lease Owner Empire Drilling Co.

Lease Name Keith Well No. 2

Office Address Wichita

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced Nov. 7 1963

Plugging completed Nov. 8 1963

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Nichols

Producing formation Depth to top Bottom Total Depth of Well 3926 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. All cells are empty.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3926 feet to surface feet for each plug set.

Sanded up to 3890', Dump 5 sacks of cement on bottom, Pulled pipe to 600' Circ. with mud, pulled pipe up to 540' pump 20 sacks of cement to 540' pulled pipe up to 150' pump 20 sacks of cement to 150'. Pulled pipe out put 10 sacks on top. Well completed.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 27 1963

11-27-1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.  
Address P.O. Box 313 Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Dan J. Kornfeld

(owner or operator) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld  
650-4th Nat'l. Bank Bldg, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 19 63



Lucille H. Harr  
Notary Public.

My commission expires October 21, 1966

15-065-19112-00-00

LOG

COMPANY: EMPIRE DRILLING COMPANY  
 CONTRACTOR: EMPIRE DRILLING COMPANY  
 FARM: KEITH #2  
 LOCATION: NE SW SW, SEC. 3-98-24W  
 GRAHAM COUNTY, KANSAS  
 COMMENCED: 12/28/54  
 COMPLETED: 1/5/55

0	TO	192
192	TO	2097
2097	TO	2134
2134	TO	2840
2840	TO	2930
2930	TO	3092
3092	TO	3270
3270	TO	3415
3415	TO	3631
3631	TO	3738
3738	TO	3800
3800	TO	3926
3926		

SURFACE HOLE  
 SHALE AND SHELLS  
 ANHYDRITE  
 SHALE AND SHELLS  
 SHALE AND LIME  
 SHALE AND SHELLS  
 LIME AND SHALE  
 SHALE AND SHELLS  
 LIME AND SHALE  
 SHALE AND LIME  
 LIME AND SHALE  
 LIME  
 R.T.D.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 NOV 27 1963  
 CONSERVATION DIVISION  
 Wichita, Kansas

SET 171' OF 8-5/8" SURFACE CASING, CEMENTED WITH 115 SACKS OF CEMENT.

ELEVATION: 2409 K.B.

TOPS: ANHYDRITE 2097'; HEEBNER 3708'; TORONTO 3732'; L.S. K.C. 3746'; R.T.D. 3926'.

SET 3921' OF 5 1/2" CASING, CEMENTED WITH 75 SACKS OF CEMENT.

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE KEITH #2, NE SW SW, SECTION 3, TOWNSHIP 9 SOUTH, RANGE 24 WEST, GRAHAM COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.



*Dan J. Kornfeld*  
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 7TH DAY OF JANUARY 1955.

MY COMMISSION EXPIRES MAY 5, 1956

*Mary Weiner*  
 NOTARY PUBLIC