

API NUMBER 15-065-22,712 ⁰⁰⁻⁰⁰
 LEASE NAME Minium
 WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

4,950 Ft. from S Section Line
3,630 Ft. from E Section Line
 SEC. 7 TWP. 9 RGE. 24 (X) or (W)
 COUNTY Graham
 Date Well Completed 6-15-93
 Plugging Commenced 6-16-93
 Plugging Completed 6-16-93

LEASE OPERATOR Staab Oil Co.
 ADDRESS 1960 280th Ave., Hays, KS. 67601
 PHONE#(913) 625-3013 OPERATORS LICENSE NO. 6037
 Character of Well D & A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-15-93 (date)
 by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filled? No If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,056'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	248'	Cmtd. w/195 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spot 25 sax cement @2,190' thru drill pipe. Push bridge plug to 1,015', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 300', spot 40 sax cement on plug thru drill pipe. Push plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Oil Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of contractor or operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 22nd day of June 1993

Ruth Phillips Notary Public
 RECEIVED JUN 23 1993
 06-23-1993
 CONSERVATION DIVISION
 Wichita, Kansas

My Commission Expires:





Shields


WELL LOG

15 065-22712-00-00

Russell, Kansas

Operator: Staab Oil Co.
 Well: Minium #1
 Commenced: June 9, 1993
 Completed: June 15, 1993
 Contractor: Shields Drilling Co.

Well Description: NW NE NW
 Sec. 7-9S-24W
 Graham Co., KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	248'	Cmtd. w/195 sax

Elevation: 2,488'

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Shale & sand	2,003'	
Shale	2,175'	
Anhydrite	2,211'	
Shale	2,802'	
Shale & lime	3,895'	
Lime	4,056'	RTD

Notes

RECEIVED
 STATE CORPORATION COMMISSION

JUN 23 1993

CONSERVATION DIVISION
 Wichita, Kansas