

10-16

249

4-070968

-00-00 R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-22,119
SW SW NW /4 SEC. 16, 09 S, 18 W
2970 feet from S section line
4950 feet from E section line

Operator license# 3456 Lease Kaba well # 1

Operator: A.F.G. Energy, Inc. County Rooks

Address: P.O. Box 605 Well total depth 3587 feet *116.57*
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
Terry W. Piesker Surface pipe 8 5/8 Inch @ 264 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 16 Month: October Year: 91

Plugging proposal received from: Terry W. Piesker

Company: A.F.G. Energy, Inc. Phone: 913-483-6213

Were: 8 5/8" 264' S.P. cwc. with 180 sks.cmt. 5 1/2" casing set at 3586' w/150 sks. cement. Perf. @ 3547' to 3277'. Casing has leak. Proposal - 400 sks. 65/35 posmix - 8% gel. - 5 sks. hulls. Spot with tubing, perforate anhy. @ 1450' and Dakota formation @ 860'. Run tubing to a minium of 3000'. Load both 5 1/2" casing and 5 1/2" x 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All], Part], None]

Completed: Hour: 1:30P.M., Day: 16, Month: October, Year: 91

Actual plugging report: A.F.G. ordered 400 sks. 65/35 posmix - 8% gel. and 5 sks. hulls. Pumped in with pump truck. Spotted and displaced cement with tubing. 1) Perferated 5 1/2" casing @ 1450' and 860'. 2) 2 3/8" tubing @ 3082' w/15 sks. cement followed w/110 sks. cement w/3 sks. hulls. 3) 2 3/8" tubing @ 1645' w/100 sks. cement. - cement circulated out of 5 1/2" casing. 4) Squeezed annulus w/100 sks. cement. Max. pressure 300 P.S.I. Cement circulated out of 5 1/2" casing. 5) Squeezed 5 1/2" casing w/75 sks. cement w/1 hull. Max. pressure 300 P.S.I. Shut in @ 150 P.S.I.

Remarks:

I did / did not observe the plugging.

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

Marion J. Schmidt

(agent)

Form CP-2/3

DATE 11-13-91 NOV 4 1991

Phil S.

INV. NO. 33683

11-4-91

WICHITA, KANSAS