

140
R

2-18-88
15-163-03543-00-00
API NUMBER 15-1953

6 031037

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NE, SEC. 34, T 9 S, R 20 (W) EX
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5258

Lease Name Coddington Well # 4

Operator: D. G. Hansen Trust

County Rooks 124.48

Name & Address Box 187

Well Total Depth 3830 feet

Logan, Ks. 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 160

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Kansas

Company to plug at: Hour: PM Day: 18 Month: Feb Year: 19 88

Plugging proposal received from Johnnie Parsons

(company name) D. G. Hansen (phone)

were: 8 5/8" set at 160' w/125 sks cwc. 5 1/2" set at 3828' w/125 sks.

Squeezed at 1765' w/635 sks Cement cwc. Order 200 sks ATL Cement Blend 65/35 Poz 10%

Gel 2% Dical. Allied Cement Co. 5 sks Hulls. OWS Water Truck and Company Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 6:00PM Day: 18 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/200 sks Cement Blend w/5 sks Hulls mixed in

(25 sks, 5 sks, 175 sks) to Max Psi 1000#. Close in Psi 800#. Tested Annulus

8 5/8" - 5 1/2" to 800#. No Gain Cement at surface released. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
04-22-1988
APR 22 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 4-26-88

INV. NO. 20453