

4-042060

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-19,003-0000

SE SE NE / 4 SEC. 34 , 09 S, 20 W
2970 feet from S section line
330 feet from E Section line

Operator license# 32432

Lease: Coddington Well # 9

Operator: Laveto Oil & Gas LLC

County: Rooks 124.09

Address: 141 W. Jackson - #1775
Chicago, Illinois 60604

Well total depth 3818 feet
Conductor Pipe: inch @ feet
Surface Pipe: 8 5/8 Inch 173 Feet

Aband. oil well X , Gas well , Input well , SWD , D & A

Plugging contractor: Swift Services License#

Address: Ness City, Kansas 67560

Company to plug at: Hour: 8:00 A.M. Day: 27 Month: July Year 2000

Plugging proposal received from: Bennie Griffin & Bill Siefers

Company: Laveto Oil - Rt 3 Box 56 - Stafford Ks 67578 Phone: 316-292-2448

Were: Ordered 350 sxs 60/40 pozmix - 10% gel - 15 sxs gel plus 800# hulls.
5 1/2" casing set at 3818' w/N/A sxs cement. Perf at 3591' - 3595'.
Perf salt at 2200' - Anhy at 1750' - Dakota at 1000' - W.L.M. 3600' - T.O.F. at 300'
Run tubing to 3590'.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:00 P.M. , Day 27 , Month: July , Year: 2000

Actual plugging report: Perf casing at 2275' - 1750' - 1000'. RIH with tubing to 3590'.
Spotted 15 sxs gel with 100# hulls (37bbbls) to load hole, followed with 60 sxs cement with
350# hulls to plug bottom. Pulled tubing to 2275+'. Spotted 200 sxs cement with 350# hulls
to circulate at surface. POOH with tubing - squeezed casing with 30 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#. Cement visible at surface in 8 5/8" S.P.

Remarks: Checked 07-28-00 - Cement top at 15' from surface.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X , NO

Plugged through TUBING CASING . Elevation: G.L.

I did[X] / did not[] observe the plugging.

Dennis L Hamel
(agent)

INVOICED
DATE 8/3/00
BILL NO. 1060295

RECEIVED
STATE CORPORATION COMMISSION
08-01-2000
AUG 1 2000
CONSERVATION DIVISION
Wichita, Kansas