

4-041792

15-065-01361-00-00

8-28

API Number: 15- - 4-30-51

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NW SE SW /4 SEC. 09, 09 S, 21 W
990 feet from S section line
1650 feet from E section line

Operator license# 6931

Lease: Clack Well # 2

Operator: Bowman Oil Company

County: Graham 120.54

Address: 805 Codell Road
Codell, Kansas 67663

Well total depth 3709 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day 28 Month: August Year 1996

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone: 913-434-7202

Were: 5 1/2" casing set at 3701' w/125 sxs cement. Perf. at 3701' - 3709'.

Anhy. at 1482' - Dakota at 950'.

Ordered 350 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Herb Deines - Dennis Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 2:15 P.M., Day 28, Month: August, Year: 1996

Actual plugging report: R.I.H. with perf - shot casing at 1482'. R.I.H. with tubing to 1480' and spotted 160 sxs cement with 250# hulls. P.O.O.H. with tubing. Squeezed casing with 160 sxs cement with 250# hulls. Max. P.S.I. 500#. S.I.P. 250#. R.U. cementers to 8 5/8" S.P. Pumped 50 sxs cement with 50# hulls. Max. P.S.I. 500#. S.I.P. 250#.

RECEIVED STATE CORPORATION COMMISSION

SEP 13 1996

9-13-96

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis J. Hamel (agent)

INVOICED

DATE 9-16-96

INV. NO. 46501

8-28