

4-041793 15-065-01360-00-00

8-28

API Number: 15- - 6-19-44

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW /4 SEC. 09, 09 S, 21 W
660 feet from S section line
1980 feet from W section line

Operator license# 6931

Lease: Clack Well # 1

Operator: Bowman Oil Company

County: Graham 121.61

Address: 805 Codell Road
Codell, Kansas 67663

Well total depth 3742 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 180 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day 28 Month: August Year 1996

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone: 913-434-7202

Were: 5 1/2" casing set at 3731' w/N/A sxs cement. Perf. at 3731' - 3742'.
Anhy. at 1750' - Dakota at 950' - W.L.M. at 3740' - T.O.F. at 950'.
Ordered 350 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 11:00 A.M., Day 28, Month: August, Year: 1996

Actual plugging report: R.U. Perf. and shot casing at 1750' and 950'. R.U. Cementers to 5 1/2" casing and squeezed as follows: 300 sxs cement down 5 1/2" casing with 450# hulls. Max. P.S.I. 600#. S.I.P. 200#. R.U. Cementers to 8 5/8" S.P. Squeezed 50 sxs cement with 50# hulls. S.I.P. 200#.

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1996

9-13-96

Remarks: Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED

DATE 9-16-96

INV. NO. 46500

8-28