

7-25

286

To: 6 070854  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- 065-22,583 -00-00  
NW SW SE, SEC. 31, T 9 S, R 21 W/E

990 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6768

Lease Name Leikam Well # 7  
County Graham 127.56

Operator: Carrie Exploration  
Name & Address 5400 24 Street  
Great Bend, Ks. 67530  
Cindy Werth

Well Total Depth 3925 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Lloyd Drilling License Number 3300  
Address St. Peter, Ks.

Company to plug at: Hour: PM Day: 25 Month: July Year: 19 90  
Jack Austin

Plugging proposal received from Lloyd Drilling Inc. (company name)  
(phone) 913-625-4968

were: 8 5/8 209 ft. s.p. cwc w/160 sks 60/40 poz 3% cc 2% gel (By Allied).  
Arb well 3916 - Elev. 2317. Anhy 1795. No circ problems.

Mud condition 45 vis. 9.2 weight. 8 water loss. Proposal 225 sks 60/40 poz 6% gel 2% cc lsk f.c.  
and 8 5/8 plug. 25 sks at 3870. 25 sks at 1800. 100 sks w/1 sk f.c. at 1040 - 40 sks at 250.

Wiper plug at 40' w/10 sks cement. 15 sks rathole. 10 sks mousehole, Spot with drill stem-mud between all plugs. Circ.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None  
Operations Completed: Hour: 1:30AM Day: 25 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Carrie ordered 225 sks 60/4 poz 6% gel 3 % cc and 8 5/8  
plug. Spotted with drill stem, mud between all plugs. 1st plug at 3870 w/25 sks cement.  
2nd plug at 1800 w/25 sks cement. 5th plug mud to 40' w/w.p. w/10 sks cement.  
3rd plug at 1040 w/100 sks cement. 15 sks in rathole (circ)  
4th plug at 250 w/40 sks cement. 10 sks mousehole (circ)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-1-90  
INV. NO. 28855  
7-25

SEP 14 1990

Signed Marion J. Schmidt (TECHNICIAN)