

8-28

4-060276

122

WR

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,588

00-00

SW NE SE /4 SEC. 31 , 09 S, 21 W
1650 feet from S section line
990 feet from E section line

Operator license# 6768

Lease Dillon well # 5

Operator: Carrie Exploration

County Graham

Address: c/o Andy Werth
P.O. Box 533
Hays, Kansas 67601

Well total depth 3923 feet ^{127.49}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Lloyd Drilling License# 3300

Address: Morland, Kansas

Company to plug at: Hour: 2:45P.M. Day: 28 Month: August Year: 91

Plugging proposal received from: Andy Werth

Company: Carrie Exploration Phone: _____

Were: Order 200 sxs. 60/40 pozmix - 6% gel. with 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: ?
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:30P.M. , Day: 28 , Month: August , Year: 91

Actual plugging report:
1st. plug at 1820' with 25 sxs.
2nd. plug at 1040' with 100 sxs. - Dakota 743' - 1043'.
3rd. plug at 260' with 40 sxs. - Surface pipe to 211'.
4th. plug at 40' with 10 sxs.

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1991

12-16-91

Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: Allied Cementing.

INVOICED I did not [] observe the plugging.

DATE 12-7-91

File S.

(agent)

INV. NO. 36202

Form CP-2/3

8-28