

6 031513

3-18

API NUMBER 15-065-20092-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

100' NW
NW SE SE, SEC. 9, T 9 S, R 22 W/EX

1060 feet from S section line
1060 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Rice Estate Well # 1

Operator: Raymond Oil Co. Inc.
Name & Address: Box 167
Lyons, Ks. 67554

County Graham 127.36
Well Total Depth 3919 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 18 Month: Mar Year: 1991

Plugging proposal received from Monty

(company name) Kelso (phone)

were: 8 5/8 set at 228 w/175 sks cwc. 5 1/2 set at 3918 w/150 sks. PBDT 3918.
Perfs 3737 1/2 - 42 1/2. TOC 3300. Order sand and common cement. Recover pipe.
Order 225 sks 65/35 poz 10% gel. 500 lbs. hulls. Allied Cement Co.
Murfin Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30PM Day: 18 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sand bottom to 3650 w/5 sks common cement on sand w/
bailer. Recovered 500 of 5 1/2 casing w/shots at 200 1000 800 500.
Cemented through casing to load hole w/50 sks cement blend. Laid down
casing. Tied onto 8 5/8 sq w/total of 225 sks cement blend to max
psi 300 lbs.. Close in psi 150 lbs
Plug complete.

RECEIVED STATE CORPORATION COMMISSION

APR 04 1991

Remarks: (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas 4-4-91

INVOICED

DATE 4-11-91
INV. NO. 31495

Handwritten initials

Signed Carl Goodrow (TECHNICIAN)