

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20705-00-00
Spot: NENENW Sec/Twnshp/Rge: 1-9S-23W
440 feet from N Section Line, 440 feet from E Section Line
Lease/Unit Name: CASEY JONES Well Number: 3-1
County: GRAHAM Total Vertical Depth: 3827 feet

Operator License No.: 31070 Conductor Pipe: Size feet:
Op Name: EAGLE RIVER ENERGY CORPORATION Surface Casing: Size 8.625 feet: 131 125 SX CMT
Address: 7060 S. YALE #609 Production: Size 4.5 feet: 3862 175 SX CMT
TULSA, OK 74136 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/03/2001 12:00 PM
Plug Co. License No.: 31070 Plug Co. Name: EAGLE RIVER ENERGY CORPORATION
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (918) 494-8928

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Work string.

124.38

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/03/2001 3:15 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 131' w/125 sxs cwc. 4 1/2" set at 3862' w/175 sxs.
PBD 3827'. Prod Perfs 3614' - 3805'.
Ran work string to 2712' - spotted cement and stage to surface.
Holes in casing between 1655' - 1695'.
Used 260 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 300#.
Squeezed 8 5/8" with 15 sxs cement blend to Max. P.S.I. 500#.
Plug complete.

INVOICED
DATE 4-11-01
INV. NO. 2001061615

RECEIVED
STATE CORPORATION COMMISSION
4/11/01 APR 11 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: LEASE ALSO KNOWN AS CASEY JONES 3-1 (SEE SCOUT CARD). ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

