

4- 031763

9-18

229  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-21,174-00-02

C NW /4 SEC. 01, 09 S, 23 W  
3960 feet from S section line  
3960 feet from E section line

Operator license# 6861

Lease Casey Jones well # 3-3

Operator: Ron's Oil Operations

County Graham

Address: R.R. 1  
Box 194  
Penokee, Kansas 67659

Well total depth 3898 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 172 feet

126.69

Aband. oil well     , Gas well     , Input well ENH X, SWD     , D & A     

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 18 Month: September Year: 92

Plugging proposal received from: Ron

Company: Ron's Oil Operations Phone:     

Were: Order 275 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Hole open. Pulled tubing and packer.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 10:45A.M., Day: 18, Month: September, Year: 92

Actual plugging report: 8 5/8" set @ 172' w/140 sx. 5 1/2" set @ 3891'  
w/175 sx. Perf. 3763' - 3820'. P.B.T.D. 3852'. Cement circulated from  
anhy. to surface. Squeezed 5 1/2" with 275 sx. cement blend with 500#  
hulls mixed in. Max. P.S.I. 1000#. Close in P.S.I. 700#.  
Test backside to 500# cwc. Plug complete.

Remarks:       
Condition of casing(in hole):GOOD X BAD      Anhy.plug:YES X NO       
Bottom plug(in place):YES     , CALC X, NO      Dakota plug:YES X, NO       
Plugged through TUBING     , CASING X. Elevation:      GL     

I did[X] / did not[      ] observe the plugging.

DATE 11-18-92

INV. NO. 36803

DEC 11 1992

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION

10/8/92  
OCT 8 1992

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED